

Strategic Charging Infrastructure Guidance

Standard Project Steps for Installing Chargepoints in SRN
Service Areas

01 February 2025

Introduction

This document outlines the standardised process for installing electric vehicle (EV) chargepoints in Service Areas across the Strategic Road Network (SRN). It is designed to provide a clear, step-by-step framework for project teams, stakeholders, and delivery partners, ensuring a consistent approach from site identification through to operational readiness.

The process is divided into five key phases — **Optioneering, Design and Approvals, Pre-Construction, Construction and Installation, and Handover and Operation** — each with defined activities, stakeholder inputs, and indicative timelines. This structured approach helps to:

- Align stakeholders early and address technical, commercial, and environmental considerations.
- Streamline approvals and procurement processes.
- Reduce project risks by incorporating connectivity, cybersecurity, and contingency planning.
- Ensure compliance with safety, quality, and performance standards.

1. Optioneering

Step 1: Optioneering (~8–12 weeks)

1.1 Site Identification and Assessment:

- Evaluate locations based on traffic flow, accessibility, and proximity to the SRN.
- Analyse demand and engage stakeholders.
- Secure initial agreements with landowners and service station operators.

1.2 Technical and Environmental Feasibility:

- Conduct site surveys and Environmental Impact Assessments (EIA).
- Assess grid connection feasibility and capacity.
- Evaluate planning permission needs.

1.3 Stakeholder Consultation:

- Engage local authorities, National Highways, and utility providers.
- Inform the public about construction timelines and impacts.
- Coordinate updates with operators and authorities.
- Address land use, safety, and traffic concerns.

1.4 Funding:

- Secure funding for the project.

2. Design and Approvals

Step 2: Design and Approvals (~2–4 weeks)

2.1 Concept Design Development:

- Draft preliminary designs for layouts, connections, and facilities.
- Confirm technical specifications and infrastructure needs.

2.2 Detailed Design Approvals:

- Finalise designs with stakeholder feedback.
- Submit planning applications and secure permits.
- Obtain approvals from National Highways and relevant authorities.

2.3 Procurement Strategy:

- Create procurement plans for contractors, equipment, and materials.
- Issue tenders and evaluate proposals.

3. Pre-Construction

Step 3: Pre-Construction (~4–6 weeks)

3.1 Site Preparation:

- Secure access agreements and operational licenses.
- Prepare the site, including groundwork and clearance.

3.2 Grid Connection:

- Finalise agreements with DNOs, iDNOs, or ICPs.
- Schedule grid connection and power supply installations.

3.3 Data Cables and Connectivity Assessment:

- Assess data cable needs.
- Consider SIM or mobile connectivity for remote payments.
- Ensure compatibility with payment platforms.

3.4 Cybersecurity Assessment:

- Assess network and payment security.
- Implement safeguards and conduct penetration testing.

3.5 Emergency Response Planning:

- Develop contingency plans for outages and failures.
- Install backup power systems.
- Train teams for rapid response.

4. Construction and Installation

Step 4: Construction and Installation (~6–12 weeks)

4.1 Civil and Electrical Works:

- Set up signage and traffic management.
- Install foundations, cabling, and electrical infrastructure.
- Assemble and install chargepoint hardware.

4.2 Testing and Commissioning:

- Conduct electrical and operational testing.
- Ensure compliance with safety and performance standards.

5. Handover and Operation

Step 5: Handover and Operation (~4–8 weeks)

5.1 Final Approvals and Handover:

- Complete inspections and obtain certifications.
- Hand over the site to the operator.

5.2 Operational Readiness:

- Activate systems, including payment and monitoring software.
- Train maintenance staff and set up support services.